17579, 17600, 17601, 17616, 17617

ALL TILE ROOF HOOK FOR BOTTOM MOUNT RAILS; ADJUSTABLE





A DIVISION OF QUICKSCREWS INTERNATIONAL CORP


TABLE OF CONTENTS

- SPEC SHEET


 QTY & MEASUREMENT INFORMATION
- INSTALLATION INSTRUCTIONS
 STEP-BY-STEP-INSTALLATION GUIDE
- TEST RESULTS
 SUCH AS: WATER, UPLIFT, COMPRESSION, ETC.
- UL CERTIFICATION
 PROOF OF UL CERTIFICATION

SPEC SHEET

Part #	Box Quantity	Screw Size	
17578	10 Hooks	N/A	
17579	1 Hook	N/A	
17616	10 Hooks; 20 Screws	5/16" x 3"	
17617	1 Hook; 2 Screws	5/16" x 3"	
17600	10 Hooks; 20 Screws	#14 x 3"	
17601	1 Hook; 2 Screws	#14 x 3"	







Phone: [844] 671-6045 | Fax: (800) 689-7975 | www.solarroofhook.com

INSTALL INSTRUCTIONS



RECOMMENDED MATERIALS

- Rafter locater
- Chalk or crayon
- Drill Bit
- Sealant compatible with roofing materials








- 2. Locate and mark the rafters
- Place the mount and predrill holes
- 4. Fill the predrilled holes with sealant
- 5. Drive the Mounting Screws
- 6. Place the tiles back over the roof mount













IF USING GALVA FLASHING

- 1. Make a cut in the paper
- 2. Apply sealant to the underside of the Galva

















BUILDING CODE LETTER



February 26, 2019

To whom this may concern,

QuickBOLT is committed to excellence. The parts tested are durable goods, meaning the material composition and detailed specifications of the parts do not change. Therefore, all stamps are current. Any part tested will have the same results no matter what year the tests are performed.

SolarRoofHook is the previous name of QuickBOLT. Any test result referencing SolarRoofHook is referring to a QuickBOLT product.

All our parts were tested by a third-party test facility, in possession of a current engineering license for the state where the tests were performed for the following.

- 1. Uplift test
- 2. Downward load test
- 3. Lateral Test Asphalt Mounts, and Metal Mounts only
- ASTM E2440 and ASTM E330 Waterproof Tests QuickBOLT only

The following is an excerpt from:

CALIFORNIA BOARD FOR PROFESSIONAL ENGINEERS AND LAND SURVEYORS guide to Engineering & Land Surveying for City and County Officials
Page 12, Line 27

27. If the license has expired between the time the engineering documents were prepared and the time when the local agency's review is performed, do the documents need to be re-sealed by a licensee with a current license? (8&P Code §§ 6733, 6735.3, 6735.4)

As long as the license was current at the time the engineering documents were prepared, the documents do not need to be re-sealed prior to review by the local agency. However, any changes (updates or modifications) to the documents that are made following the review by the local agency would have to be prepared by a licensed engineer with a current license and those changes would have to be signed and sealed.

We trust the information provided will resolve any request for the test reports submitted to have a stamp from the current year.

Regards.

Rick Gentry

Executive Vice President

ENGINEERING REPORT



Tel: (510) 420-8190 FAX: (510) 420-8186 e-mail: info@appmateng.com

April 1st, 2015

Mr. Rick Gentry SolarRoofHook a division of Quickscrews International Corp. 5830 Las Positas Road Livermore, CA 94551

Project Number 115169C

STA18038 All Tile Adjustable 180° Roof Hook Laboratory Load Testing Subject:

Dear Mr. Gentry:

As requested, Applied Materials & Engineering, Inc. (AME) has completed load-testing the All Tile Adjustable 180° roof hook (see Appendix A, Figure 1). The purpose of our testing was to evaluate the compressive, and tensile (uplift) load capacity of the All Tile Adjustable 180° roof hook attached to a 2"x4" Douglas Fir Rafter using two #14x3" screws.

SAMPLE DESCRIPTION

Mockup samples were assembled in our laboratory on March 26th & 27th, 2015. Mockup configuration consisted of three 16" long rafters at 4.5"o.c., screwed to 1/2" Structural I plywood. The All Tile Adjustable 180° roof hook is attached through the plywood into a rafter with two fasteners. The roof hook is positioned in the center of the base plate with the fasteners installed at the farthest end.

TEST PROCEDURES & RESULTS

1. Compressive Load Test

A total of three tests were conducted for compressive load capacity on March 26th, 2015 using a United Universal testing machine. Samples were rigidly attached to the testing machine and a compressive load was applied to the hook. The samples were loaded in compression at a constant rate of axial deformation of 0.09 in. /min. without shock until the hook was bent and came in contact with the test board, displacement at maximum load was recorded. Based on the above testing, the average maximum compression load of the All Tile Adjustable 180° roof hook attached to a 2*x4" Douglas Fir rafter using two #14x 3" screws was determined to be 301 lbf. Detailed results are provided in Table I. Test setup and mode of failure are provided in Appendix B, Figure 1.

The specific gravity and moisture content of the rafter was tested in accordance with ASTM D2395, Method A (oven-dry). The specific gravity and moisture content were determined to be 0.375 and 13.9 %, respectively.

Page 1 of 9

APPLIED WATERIALS & ENGINEERING, INC.

Project Number 115169C

Mr. Rick Gentry QUICKSCREWS INTERNATIONAL 5830 Las Positas Road Livermore, CA 94551

2. Tensile (Uplift) Load Test

A total of three tests were conducted for compressive load capacity on March 27th, 2015 using a United Universal testing machine. Samples were rigidly attached to the testing machine and an uplift load was applied to the hook. The samples were loaded in tension at a constant rate of axial deformation of 0.09 in. /min. without shock until failure occurred; displacement at maximum load was recorded. Based on the above testing, the average maximum uplift load of the All Tile Adjustable 180° attached to a 2"x4" Douglas Fir rafter using two #14x3" screws was determined to be 2041 lbf. Detailed results are provided in Table II. Test setup and mode of failure are provided in Appendix B, Figure 2.

The specific gravity and moisture content of the rafter was tested in accordance with ASTM D2395, Method A (oven-dry). The specific gravity and moisture content were determined to be 0.388 and 15.6 %, respectively.

Respectfully Submitted,

APPLIED MATERIALS & ENGINEERING, INC.

Reviewed By:

rindipal

emen Tajirian, Ph.D., P.E.

Mohammed Faryaz Laboratory Manager Mo. 35538

Exp. 8590/15

APPLIED MATERIALS & INGENTIFICADO, INC.

TABLE I

COMPRESSIVE LOAD TEST RESULTS

ALL TILE ADJUSTABLE 180° ROOF HOOK (PART # STA18038)

PROJECT NUMBER 115169C

SAMPLE ID	MAXIMUM COMPRESSIVE LOAD (lbf)	DISPLACEMENT AT MAXIMUM LOAD (in.)	FAILURE MODE
C-1	308	2.0	Hook contact w/Plywood
C-2	291	2.4	Hook contact w/Plywood
C-3	304	2.1	Hook contact w/Plywood
AVERAGE	301	2.2	

TABLE II


TENSILE (UPLIFT) LOAD TEST RESULTS

ALL TILE ADJUSTABLE 180° ROOF HOOK (PART # STA18038)

PROJECT NUMBER 115169C

SAMPLE ID	MAXIMUM TENSILE LOAD (lbf)	DISPLACEMENT AT MAXIMUM LOAD (in.)	FAILURE MODE
T-1	2216	7.2	Fastener pullout
T-2	1708	6.5	Fastener pullout
T-3	2199	7.2	Fastener pullout
AVERAGE	2041	6.9	

All Tile Adjustable 180 Compression #1



Inmon: PS Done: 3/24

LAB EQUIPMENT USED

Compression Mechanic:
RES SIN 070100000077


ELE SIN 070100000077

United SIN 4019HI 1075

Mecausoment:
Colliper SIN

Other:

All Tile Adjustable 180 Compression #2



Initials: Done: 3144

LAB EQUIPMENT USED

Compression Machine:
ELE SIN 070100000077

ELE SIN 00-13


SAIEC SIN 400HVL1035

United SIN 890212

Measurement:
Colliper SIW

Other:

All Tile Adjustable Compression #3



Initials Date 2/27


LAS EQUIPMENT USED
Compression Macrine:
ELE SIN 0701060000077

ELE SIN 00-13


SATEC SIN 400HM 10/15
United SIN 890212

Mediumment:
Colleger SIN ______
Other:

All Tile Adjustable 180 Uplift #1




All Tile Adjustable 180 Uplift #2



Initials: DS Dohe: 3/27
LAB EQUIPMENT USED
Compression Machine:
ELE SIN 070100000077
ELE SIN 00-13
SATEC SIN 400HY,1075
United SIN 990212
Modulerment:
Caliper SIN
Other:

All Tile Adjustable 180 Uplift #3



UL CERTIFICATION

CERTIFICATE OF COMPLIANCE

Certificate Number 20180725-E493748
Report Reference E493748-20170817

Issue Date 2018-JULY-25

Issued to: SolarRoofHook, a Division of Quickscrews International Corp.

5830 Las Positas Rd, Livermore CA 94551

This is to certify that COMPONENT - Mi representative samples of CLAMPING DEVICE

COMPONENT - MOUNTING SYSTEMS, MOUNTING DEVICES, CLAMPING DEVICES AND GROUND LUGS FOR USE WITH

PHOTOVOLTAIC MODULES AND PANELS Refer to Addendum Page for Models/Product.

Have been investigated by UL in accordance with the

Standard(s) indicated on this Certificate.

Standard(s) for Safety: UL 2703 Standard for Mounting Systems, Mounting

Devices, Clamping/Retention Devices, and Ground Lugs for

Use with Flat-Plate Photovoltaic Modules and Panels.

Additional Information: See the UL Online Certifications Directory at

www.ul.com/database for additional information

Only those products bearing the UL Certification Mark should be considered as being covered by UL's Certification and Follow-Up Service.

The UL Recognized Component Mark generally consists of the manufacturer's identification and catalog number, model number or other product designation as specified under "Marking" for the particular Recognition as published in the appropriate UL Directory. As a supplementary means of identifying products that have been produced under UL's Component Recognition Program, UL's Recognized Component Mark:

10. may be used in conjunction with the required Recognized Marks. The Recognized Component Mark is required when specified in the UL Directory preceding the recognitions or under "Markings" for the individual recognitions.

Recognized components are incomplete in certain constructional features or restricted in performance capabilities and are intended for use as components of complete equipment submitted for investigation rather than for direct separate installation in the field. The final acceptance of the component is dependent upon its installation and use in complete equipment submitted to UE LLC.

Look for the UL Certification Mark on the product.

Bamely

14,440

Any intermediate and incompanies incoming 65, flats working are provided on behalf of 65, U.S. (EV, or any Authorities continue of 66, For guessions, process



CERTIFICATE OF COMPLIANCE

20180725-E493748 Certificate Number Report Reference Issue Date

E493748-20170817 2018-JULY-25

This is to certify that representative samples of the product as specified on this certificate were tested according to the current UL requirements.

Models/Product

USR - Component, Roof Mounting Hook Units, Models 15891 15893 15987 16000 16988 16990 16991 16993 17508 17509 17510 17511 17512 17513 17514 17515 17516 17517 17518 17519 17520 17521 17522 17523 17524 17525 17526 17527 17536 17537 17538 17539 17540 17541 17542 17543 17544 17545 17546 17547 17548 17549 17550 17551 17552 17553 17554 17555 17556 17558 17559 17560 17568 17560 17570 17571 17572 17573 17574 17575 17576 17577 17578 17570 17580 17585 17585 17587 17588 17589 17592 17596 17600 17601 17606 17607 17608 17609 17610 17611 17612 17613 17614 17615 17616 17617 17618 17620 17621 17622 17623 17624 17625 17626 17627 17628 17629 17630 17631 17632 17633 17636 17637 17638 17639 17642 17643 17646 17647 17648 17649 17650 17651 17659 17664 17667 17669 17670 17671 17672 17673 17678 17679 17680 17681 17686 17687 17688 17689 17700 17701 17702 17703 17704 17705 17706 17707 17708 17709 17710 17711 17712 17717 17718 17759 15891-10 15891BLK-10 15967A 15967B 17667SS 17672SS 17680SS 17688SS 17713SS 17720 17721SS 17723 17724SS 17726 17727SS 17729 17730SS 15894SS 1589138 15987B38.





Page 2 of 2